



NOTE:  
NOT ALL DETAILS MAY BE USED ON THIS PROJECT.

**FIRE ALARM SYSTEM - SEQUENCE OF OPERATION**

FIRE ALARM SYSTEM SEQUENCE OF OPERATION	ACTIVATE AUDIO/VISUAL DEVICES	GENERAL ALARM AT FACP	SUPERVISORY ALARM AT FACP	NOTIFY CENTRAL STATION	ALARM AT ANNUNCIATOR	SHUTDWN HVAC UNIT
WATER FLOW	X	X		X	X	
VALVE SUPERVISION			X	X	X	
MANUAL PULL STATIONS	X	X		X	X	
HVAC DUCT SMOKE DETECTORS			X	X	X	X
AREA SMOKE DETECTOR	X	X		X	X	
HOOD SUPPRESSION SYSTEM	X	X		X	X	
HVAC SHUT DOWN MANUAL PUSHBUTTON DEPRESSED			X	X	X	X

NOTE: THIS DOCUMENT MAY HAVE BEEN ELECTRONICALLY TRANSMITTED. IF UNSIGNED, IT CANNOT BE FILED FOR PUBLIC RECORD. PUBLIC RECORD FILINGS REQUIRE SIGNED AND SEALED DOCUMENTS.

PROJECT MANAGER  
Kasey Steyn  
JOB NO.  
12-07148-02  
SCL. BY  
MRY / CDB

HARRIS TEETER #149  
NORTHWOOD SQUARE  
ROCK HILL, SC

REVISIONS

No.	Date

DRAWING NAME  
**FIRE ALARM DETAILS**