



- GENERAL NOTES:**
- THE GENERAL CONTRACTOR SHALL COORDINATE THE RELOCATION OF EXISTING PHONE LINES AND OUTLETS WITH HT PROJECT MANAGER, STORE MANAGEMENT, AND PHONE VENDOR.
 - THE GENERAL CONTRACTOR SHALL REMOVE ALL CARLS FROM FLOOR AND CEILING WHERE EXISTING WALLS AND/OR CASES ARE REMOVED.
 - EXISTING HALL APPLIED AND HUNG DECOR REMOVAL AND/OR RELOCATION TO BE PERFORMED BY THE GENERAL CONTRACTOR. G.C. TO REPAIR WALLS AS NECESSARY ONCE DECOR HAS BEEN REMOVED. COORDINATE WITH HT PROJECT MANAGER, DECOR CONTRACTOR, DECOR CONTRACTOR AND HT PROJECT MANAGER.
 - GENERAL CONTRACTOR TO COORDINATE WITH HT PROJECT MANAGER THE REMOVAL AND/OR SALVAGING OF EXISTING EQUIPMENT AND CASES. ALL EQUIPMENT AND CASES TO BE SALVAGED BUT NOT REINSTALLED ARE TO BE TURNED OVER TO HT PROJECT MANAGER FOR REMOVAL FROM JOBSITE.
 - GENERAL CONTRACTOR SHALL PATCH EXISTING FLOORING WHERE ITEMS ARE TO BE REMOVED. MATCH EXISTING MATERIALS. COORDINATE WITH ENGINEERING DRAWINGS.
 - R.I.C. IS RESPONSIBLE FOR THE REMOVAL, RELOCATION AND DISPOSAL OF ALL EXISTING EQUIPMENT, CASES, FREEZER COOLERS, CHECK STANDS ETC. AND GONDOLAS. G.C. IS RESPONSIBLE FOR REMOVAL AND DISPOSAL OF MILL WORK, DRY WALL, STUDS, WIRE, HUNG SCREWS ETC. THAT MAY NEED TO BE REMOVED FOR R.I.C. TO PERFORM HIS TASK. G.C. SHALL PROVIDE DUMPSTER FOR R.I.C.'S MATERIAL DISPOSAL.
- KEY NOTES:**
- REMOVE EXISTING TOILET ROOM PARTITIONS. VERIFY EXTENTS IN FIELD.
 - REMOVE EXISTING MILLWORK.
 - EXISTING EQUIPMENT/CASES TO BE RELOCATED PER NEW FIXTURE PLAN BY R.I.C. COORDINATE WITH HT PROJECT MANAGER.
 - EXISTING EQUIPMENT/CASE TO BE REMOVED BY R.I.C.
 - REMOVE EXISTING HALL.
 - REMOVE EXISTING DOOR.
 - REMOVE EXISTING COOLERS/ FREEZER BY R.I.C.
 - REMOVE EXISTING WINDOW.
 - EXISTING CASE ENDCAP TO BE RELOCATED PER NEW FIXTURE PLAN BY R.I.C. COORDINATE WITH HT PROJECT MANAGER.
 - G.C. TO DEMO ALL EXISTING HANGSCOT AND REPAIR WALL.
 - REMOVE ALL EXISTING HALL MOUNTED OR HANGING DECOR. REPAIR ALL WALL DAMAGE TO FINISHED SURFACE.
 - ALL EXISTING SIGNAGE WILL BE REMOVED BY OTHERS. G.C. TO REPAIR ALL HALL DAMAGE OR HOLES WITH SURFACE MATCHING MATERIALS.
 - REMOVE IMPACT DOOR FRAME. COORDINATE WITH STRUCTURAL FOR NEW FRAME INSTALLATION.
 - REMOVE EXISTING COOLERS/ FREEZER DOOR BY R.I.C. DOOR. VERIFY EXTENTS IN FIELD.
 - REMOVE EXISTING HALL FOR INSTALLATION OF NEW DOOR. VERIFY EXTENTS IN FIELD.
 - REMOVE EXISTING HALL PAPER. PATCH HALL FOR NEW PAINT.
 - G.C. SHALL REMOVE ALL HALLS, DOORS, PLY WOOD, CEILING ETC. IN THE MOTOR ROOM. COORDINATE WITH R.I.C. FOR EQUIPMENT REMOVAL. LEAVE MOTOR ROOM TO BARE STRUCTURE AND CLEAN PRIOR TO NEW EQUIPMENT INSTALLATION.
- LEGEND**
- EXISTING EQUIPMENT, WALLS TO BE REMOVED
 - EXISTING TO REMAIN
 - EXISTING TO BE RELOCATED

DEMO FIXTURE PLAN
SCALE: 3/32" = 1'-0"

PROJECT MANAGER:
Robyn Phoebe
JOB NO.:
18-0445-02

DR. BY:
TASH

REVISIONS:

No.	Date
1	10/24/2018
2	10/24/2018